

200

FOR PERMITTING ONLY

NOT FOR CONSTRUCTION

No. 6091_CVR(PENNY)_R1.DWG [CVR]

ZPTII-241 SOLAR ARRAY
5 & 5R HATFIELD STREET

(ASSESSOR MAP K - LOT 33
& MAP G LOT 76-1)

-PERMIT SITE PLANS-

MODULES	DC POWER
14,924±	4.75±MW

IOCATED IN
WILLIAMSBURG, MASSACHUSETTS

DATE: FEBRUARY 19, 2019

APPLICANT:

ZPT ENERGY SOLUTIONS II, LLC 6 PARK AVENUE, SUITE 100, LOWER LEVEL WORCESTER, MASSACHUSETTS 01605

RECORD OWNERS:

PENELOPE JOHNSON 5 & 5R HATFIELD STREET WILLIAMSBURG, MASSACHUSETTS 01096



LAND SURVEYOR/SITE CIVIL ENGINEER:

ENVIRONMENTAL CONSULTANT:



LEC ENVIRONMENTAL CONSULTANTS, INC.

100 GROVE STREET, SUITE 302

WORCESTER, MA 01605

TEL: (508) 753-3077 FAX: (508) 753-3177

WWW.LECENVIRONMENTAL.COM

DRAWING INDEX:


TOWN CLERK

"THIS PLAN IS SUBJECT TO A SPECIAL PERMIT DATED _____

"THIS PLAN IS SUBJECT TO A SITE PLAN REVIEW DATED _____

DRAWING IND	$\frac{EX:}{}$	
SHEET 1	COVER SHEET & LOCUS CONTEXT .	MAP
SHEET 2	RECORD CONDITIONS PLAN OF LAN	VD
SHEET 3	SITE OVERVIEW	
SHEET 4	SITE LAYOUT	
SHEET 5	GRADING & UTILITY PLAN 1	
SHEET 6	GRADING & UTILITY PLAN 2	
SHEET 7	GRADING & UTILITY PLAN 3	
SHEET 8	WETLAND CROSSING	
SHEET 9	BASIN DETAIL 1	
SHEET 10	BASIN DETAIL 2	
SHEET 11	PHASING PLAN	
SHEET 12	EROSION & SEDIMENT PLAN 1	
SHEET 13	EROSION & SEDIMENT PLAN 2	APPROVED BY:
SHEET 14	EROSION & SEDIMENT PLAN 3	WILLIAMSBURG ZONING BOARD OF APPEALS
SHEET 15	NOTES & DETAILS	
SHEET 16	DETAILS	
	_	
I, MASSACHUSETTS HEREE	CLERK OF THE TOWN OF WILLIAMSBURG, BY CERTIFY THAT THE NOTICE OF APPROVAL OF	
BEEN RECEIVED AND RA	LIAMSBURG ZONING BOARD OF APPEALS HAS ECORDED AT THE OFFICE AND NO NOTICE OF	
APPEAL WAS RECEIVED RECEIPT AND RECORDIN	DURING TWENTY DAYS NEXT AFTER SUCH NG OF SAID NOTICE.	

DATE





WILLIAMSBUF (HAMF


FEBRUARY 19, 201 1"= 200'


SHEET No. 2 of 16


PROJECT No.























STABILIZATION HAS BEEN COMPLETED (AS LISTED ABOVE), ARRAY CONSTRUCTION MAY BEGIN. CONTRACTOR SHALL HAVE

FLEXIBILITY TO BEGIN ARRAY CONSTRUCTION IN PHASE I, II OR III OUT OF SEQUENCE AS LONG AS IT IS NOT TO THE

DETRIMENT OF EROSION AND SEDIMENTATION CONSIDERATION

<u>SITE PREPARATION SHALL BE CONDUCTED IN MULTIPLE PHASES IN ORDER TO MAXIMIZE EROSION AND SEDIMENTATION CONTROL</u>

- 1. ESTABLISH PHASE I EROSION AND SEDIMENTATION CONTROL MEASURES (HAYBALES, SILT FENCE AND FILTERMITT) AS DEPICTED ON SHEETS 12-14 AROUND AREAS OF DISTURBANCE AND MAINTAIN THROUGHOUT CONSTRUCTION IN ACCORDANCE WITH LOCAL REQUIREMENTS. PERFORM INSPECTIONS, REPAIR IF NECESSARY, AND DOCUMENT AFTER EACH PRECIPITATION EVENT OF 0.25-INCHES OR GREATER.
- 2. PERFORM LIMITED CLEARING ACTIVITIES IN ORDER TO CONSTRUCT GRAVEL DRIVE.
- 3. SITE PREPARATION SHALL INCLUDE CLEARING AND REMOVAL OF EXISTING VEGETATION AND DEBRIS. ALL TREES, STUMPS, BRUSH, SHRUBS, ROOTS, GRASS, WEEDS, RUBBISH, BITUMINOUS PAVEMENT, STONES LARGER THAN 2-IN. IN THE LARGEST DIAMETER AND OTHER OBJECTIONABLE MATERIAL SHALL BE REMOVED AND DISPOSED OF FROM AREAS TO BE FILLED AND COMPACTED. AREAS OUTSIDE OF THE LIMITS OF WORK SHALL BE PROTECTED FROM DAMAGE. NO STUMPS, TREES, LIMBS, OR BRUSH SHALL BE BURIED IN ANY FILLS OR EMBANKMENTS.
- 4. CONSTRUCT INFILTRATION BASINS AND SWALE AS SHOWN ON PLANS.
- 5. FOR AREAS WHERE NO GRADING IS PROPOSED, REPAIR UNEVEN AREAS WITHIN LIMITS OF THE SOLAR DEVELOPMENT, AS NECESSARY TO CREATE A TOLERABLE GROUND SURFACE. GENERAL TOLERANCE FOR ALLOWABLE GROUND SLOPE IS TWO FOOT VERTICAL CHANGE OVER A 20 FOOT HORIZONTAL RUN [NOTE THAT THIS REFERS TO THE ALLOWABLE LONGITUDINAL SLOPE (I.E., ALONG THE CONTOUR) AND NOT THE INCLINATION OF THE EXPOSURE (I.E., PERPENDICULAR TO THE CONTOUR)].
- 6. UPON SIGNS OF CONCENTRATED FLOW BY EVIDENCE OF GULLYING OR RILLING IN DISTURBED AREAS, HAYBALES, OR APPROVED EQUAL, SHALL BE PLACED IN THESE AREAS, SPACED EVERY 50' IN THE UPGRADIENT SLOPE.
- 4. ALL DISTURBED AREAS SHALL BE STABILIZED WITH SEED MIX GUIDELINES AS NOTED ON SHEET 15. IN THE EVENT THAT THE SEEDING FALLS OUTSIDE OF THE RECOMMENDED SEEDING DATES, DISTURBED AREAS SHALL BE RE-ESTABLISHED USING ALTERNATIVES METHODS AS APPROVED BY THE PROJECT SITE ENGINEER.

<u>PHASE II:</u>


- 1. ESTABLISH PHASE II EROSION AND SEDIMENTATION CONTROL MEASURES (HAYBALES, FILTERMITT & SILT FENCE) AS DEPICTED ON THE PLANS AND AROUND AREAS OF DISTURBANCE AND MAINTAIN THROUGHOUT CONSTRUCTION IN ACCORDANCE WITH LOCAL REQUIREMENTS. PERFORM INSPECTIONS, REPAIR IF NECESSARY, AND DOCUMENT AFTER EACH PRECIPITATION EVENT OF 0.25-INCHES OR GREATER (PHASE I EROSION CONTROL IS TO REMAIN IN PLACE AND MAINTAINED AS DESCRIBED ABOVE).
- 2. REPEAT STEPS 3, 4, 5 AND 6 FROM PHASE I FOR PHASE III.
- 3. ARRAY CONSTRUCTION AS SHOWN.
- 4. ALL DISTURBED AREAS SHALL BE STABILIZED WITH SEED MIX GUIDELINES AS NOTED ON SHEET 15. IN THE EVENT THAT THE SEEDING FALLS OUTSIDE OF THE RECOMMENDED SEEDING DATES, DISTURBED AREAS SHALL BE RE-ESTABLISHED USING ALTERNATIVES METHODS AS APPROVED BY THE PROJECT SITE ENGINEER.

- 1. ESTABLISH PHASE III EROSION AND SEDIMENTATION CONTROL MEASURES (HAYBALES, FILTERMITT & SILT FENCE) AS DEPICTED ON THE PLANS AND AROUND AREAS OF DISTURBANCE AND MAINTAIN THROUGHOUT CONSTRUCTION IN ACCORDANCE WITH LOCAL RÉQUIREMENTS. PERFORM INSPECTIONS, REPAIR IF NECESSARY, AND DOCUMENT AFTER EACH PRECIPITATION EVENT OF 0.25-INCHES OR GREATER (PHASE I & II EROSION CONTROL IS TO REMAIN IN PLACE AND MAINTAINED AS DESCRIBED ABOVE).
- 2. PERFORM LIMITED CLEARING ACTIVITIES IN ORDER TO CONSTRUCT GRASS PATH.
- 3. REPEAT STEPS 3, 5 AND 6 FROM PHASE I FOR PHASE III.
- 4. PERFORM VEGETATION MANAGEMENT WITHIN AREAS AS SHOWN ON SHEET 4.
- 5. ARRAY CONSTRUCTION AS SHOWN.
- 6. ALL DISTURBED AREAS SHALL BE STABILIZED WITH SEED MIX GUIDELINES AS NOTED ON SHEET 15. IN THE EVENT THAT THE SEEDING FALLS OUTSIDE OF THE RECOMMENDED SEEDING DATES, DISTURBED AREAS SHALL BE RE-ESTABLISHED USING ALTERNATIVES METHODS AS APPROVED BY THE PROJECT SITE ENGINEER.

PHASE IV:

- 1. ESTABLISH PHASE IV EROSION AND SEDIMENTATION CONTROL MEASURES (HAYBALES, FILTERMITT & SILT FENCE) AS DEPICTED ON THE PLANS AND AROUND AREAS OF DISTURBANCE AND MAINTAIN THROUGHOUT CONSTRUCTION IN ACCORDANCE WITH LOCAL REQUIREMENTS. PERFORM INSPECTIONS, REPAIR IF NECESSARY, AND DOCUMENT AFTER EACH PRECIPITATION EVENT OF 0.25-INCHES OR GREATER (PHASE I, II & III EROSION CONTROL IS TO REMAIN IN PLACE AND MAINTAINED AS DESCRIBED ABOVE).
- 2. PERFORM LIMITED CLEARING ACTIVITIES IN ORDER TO CONSTRUCT GRAVEL DRIVE AND GRASS PATH.
- 3. REPEAT STEPS 3, 5 AND 6 FROM PHASE I FOR PHASE IV.
- 4. PERFORM VEGETATION MANAGEMENT WITHIN AREAS AS SHOWN ON SHEET 4.
- 5. ARRAY CONSTRUCTION AS SHOWN.
- ALL DISTURBED AREAS SHALL BE STABILIZED WITH SEED MIX GUIDELINES AS NOTED ON SHEET 15. IN THE EVENT THAT THE SEEDING FALLS OUTSIDE OF THE RECOMMENDED SEEDING DATES, DISTURBED AREAS SHALL BE RE-ESTABLISHED USING ALTERNATIVES METHODS AS APPROVED BY

- ESTABLISH PHASE V EROSION AND SEDIMENTATION CONTROL MEASURES (HAYBALES, FILTERMITT & SILT FENCE) AS DEPICTED ON THE PLANS AND AROUND AREAS OF DISTURBANCE AND MAINTAIN THROUGHOUT CONSTRUCTION IN ACCORDANCE WITH LOCAL REQUIREMENTS. PERFORM INSPECTIONS, REPAIR IF NECESSARY, AND DOCUMENT AFTER EACH PRECIPITATION EVENT OF 0.25-INCHES OR GREATER (PHASE I, II, III & IV EROSION CONTROL IS TO REMAIN IN PLACE AND MAINTAINED AS DESCRIBED ABOVE).
- 2. PERFORM LIMITED CLEARING ACTIVITIES IN ORDER TO CONSTRUCT GRASSED ACCESS PATH.
- 3. REPEAT STEPS 3, 5 AND 6 FROM PHASE I FOR PHASE V.
- 4. PERFORM VEGETATION MANAGEMENT WITHIN AREAS AS SHOWN ON SHEET 4.
- 5. ARRAY CONSTRUCTION AS SHOWN.
- 6. ALL DISTURBED AREAS SHALL BE STABILIZED WITH SEED MIX GUIDELINES AS NOTED ON SHEET 15. IN THE EVENT THAT THE SEEDING FALLS OUTSIDE OF THE RECOMMENDED SEEDING DATES, DISTURBED AREAS SHALL BE RE-ESTABLISHED USING ALTERNATIVES METHODS AS APPROVED BY THE PROJECT SITE ENGINEER.
- 7. REMOVE ANY ACCUMULATED SEDIMENT FROM TEMPORARY SEDIMENTATION BASINS. BRING TEMPORARY SEDIMENTATION BASINS TO GRADE AND SEED.
- 8. UPON COMPLETION OF CONSTRUCTION ACTIVITIES WITHIN THE LIMIT OF WORK, THE CONTRACTOR SHALL EFFECTIVELY AND PERMANENTLY STABILIZE THE SITE AND ALL VEGETATIVE COVER SHALL BE RE-ESTABLISHED TO THE SATISFACTION OF TOWN AUTHORITIES.



DWG. No. 6091_SITE(PENNY).DWG [PHASING 100


FOR PERMITTING ONLY NOT FOR CONSTRUCTION





FEBRUARY 19, 201 1"=100'

SHEET No. 11 of 16

PROJECT No.







- 1. EXISTING GROUND WITHIN THE PROPOSED CHAINLINK FENCE SHALL BE CLEARED, STUMPED AND RE-GRADED TO ELIMINATE MINOR SURFACE DISTURBANCES. RE-VEGETATION OF THE SITE SHALL BE ESTABLISHED WITH LOW GROWTH GROUND COVER.
- 2. THE PROPOSED TREE CLEARING ALSO DEPICTS THE LIMIT OF WORK TO BE PERFORMED ON THE PROJECT SITE. NO TREES OUTSIDE THE DESIGNATED LIMIT OF WORK LINE ARE TO BE REMOVED BY THE CONTRACTOR.
- 3. COMMON FILL (SITE GRADING AREAS) SHALL CONSIST OF MINERAL SOIL SUBSTANTIALLY FREE FROM ORGANIC MATERIALS, LOAM, WOOD TRASH AND OTHER OBJECTIONABLE MATERIALS WHICH MAY BE COMPRESSIBLE OR WHICH CANNOT BE PROPERLY COMPACTED. SELECT COMMON FILL SHALL NOT CONTAIN STONES LARGER THAN 2-IN. IN LARGEST DIAMETER AND SHALL HAVE A MAXIMUM OF 75% PASSING THE NO. 40 SIEVE AND A MAXIMUM OF 20% PASSING THE NO. 200 SIEVE. SELECT COMMON FILL SHALL NOT CONTAIN GRANITE BLOCKS, BROKEN CONCRETE, MASONRY RUBBLE OR OTHER SIMILAR MATERIALS. IT SHALL HAVE PHYSICAL PROPERTIES SUCH THAT IT CAN BE READILY SPREAD AND COMPACTED DURING FILLING, SNOW, ICE AND FROZEN SOIL WILL NOT BE PERMITTED. SOIL EXCAVATED FROM THE STRUCTURE AREAS AND WHICH MEETS THE ABOVE REQUIREMENTS
- 4. ORDINARY FILL SHALL BE WELL GRADED, NATURAL INORGANIC SOIL, FREE OF ORGANIC OR OTHER WEAK OR COMPRESSIBLE MATERIALS, FROZEN MATERIALS, AND OF STONES LARGER THAN TWO THIRDS (%) THE LIFT THICKNESS. IT SHALL BE OF SUCH NATURE AND CHARACTER THAT IT CAN BE COMPACTED TO THE SPECIFIED DENSITIES IN A REASONABLE LENGTH OF TIME. IT SHALL BE FREE OF PLASTIC CLAY, OF ALL MATERIALS SUBJECT TO DECAY, DECOMPOSITION, OR DISSOLUTION, AND OF CINDERS OR OTHER MATERIALS THAT WILL CORRODE PIPING OR OTHER METAL. IT SHALL HAVE A MINIMUM DRY DENSITY OF NOT LESS THAN 120 POUNDS PER CUBIC FOOT. MATERIAL FROM EXCAVATION ON THE SITE MAY BE USED AS ORDINARY FILL IF IT MEETS THE ABOVE REQUIREMENTS. ORDINARY FILL SHALL HAVE A MAXIMUM OF 60% PASSING THE #40 SIEVE, AND A MAXIMUM OF 20% PASSING THE #200 SIEVE. IT SHOULD NOT CONTAIN BROKEN CONCRETE, MASONRY RUBBLE OR OTHER "SIMILAR MATERIALS, AND SHALL HAVE PHYSICAL PROPERTIES SUCH THAT IT CAN BE READILY SPREAD AND COMPACTED DURING FILLING. SNOW, ICE AND FROZEN SOIL SHALL NOT BE PERMITTED.
- 5. SELECT COMMON FILL (ROADWAY AREAS) SHALL BE PLACED IN LAYERS HAVING A MAXIMUM THICKNESS OF 8 IN. MEASURED BEFORE COMPACTION. EACH LAYER OF FILL SHALL BE COMPACTED TO AT LEAST 95 PERCENT OF MAXIMUM DRY DENSITY DETERMINED BY THE ASTM D1557. COMPACTION OF STRUCTURAL FILL SHALL CONSIST OF FULLY LOADED TEN WHEEL TRUCKS, A TRACTOR DOZER WEIGHING AT LEAST 30,000 LBS AND OPERATED AT FULL SPEED, A HEAVY VIBRATORY ROLLER, OR OTHER METHOD ONLY AS APPROVED BY THE ENGINEER. COMPACTION OF SELECT COMMON FILL IN CONFINED AREAS ADJACENT TO STRUCTURES SHALL BE ACCOMPLISHED BY HAND OPERATED VIBRATORY EQUIPMENT OR MECHANICAL TAMPERS APPROVED BY THE ENGINEER. AS A MINIMUM, COMPACTION OF SELECT COMMON FILL SHALL CONSIST OF FOUR COVERAGES OF THE APPROVED EQUIPMENT.
- 6. SITE PREPARATION SHALL INCLUDE CLEARING, GRUBBING, DELETERIOUS SOILS, VEGETATION AND DEBRIS. ALL TREES, STUMPS, BRUSH, SHRUBS, ROOTS, GRASS, WEEDS, RUBBISH, STONES LARGER THAN 2-IN. IN THE LARGEST DIAMETER AND OTHER OBJECTIONABLE MATERIAL SHALL BE REMOVED AND DISPOSED OF FROM AREAS TO BE FILLED AND COMPACTED. AREAS OUTSIDE OF THE LIMITS OF WORK SHALL BE PROTECTED FROM DAMAGE AND NO EQUIPMENT OR MATERIALS SHALL BE STORED IN THESE AREAS. NO STUMPS, TREES, LIMBS, OR BRUSH SHALL BE BURIED IN ANY FILLS OR EMBANKMENTS.
- 7. EROSION AND SEDIMENT CONTROL, BOTH DURING AND AFTER CONSTRUCTION, SHALL BE PROVIDED AS REQUIRED TO RETAIN SEDIMENT ONSITE, AND TO CONTROL EROSION OF EMBANKMENTS, TEMPORARY AND FINAL EXPOSED SLOPES, AND TEMPORARY MATERIAL STOCKPILE(S). SILT FENCES, CHECK DAMS, DRAINAGE DITCHES OR SWALES, TEMPORARY SEEDING, AND PRE-MANUFACTURED TEXTILES, GEOTUBES, GEOGRID, CELLULAR GEOWEB, ETC., SHALL BE UTILIZED AS APPROPRIATE. EROSION AND SETTLEMENT CONTROL MEASURES SHALL BE IN ACCORDANCE WITH ALL PERMITS AND CODES AND THIS SPECIFICATION. DURING THE EXCAVATION OF THE WORK AT THE SITE, OPERATIONS SHALL BE CONTINUOUSLY MONITORED TO AVOID THE CREATION OF CONDITIONS THAT COULD LEAD TO EXCESSIVE EROSION OF SOIL WITH SURFACE RUNOFF FROM THE WORK AREAS. CONTROLS SHALL BE PROVIDED TO PROTECT THE WATER QUALITY AND SHALL BE IN ACCORDANCE WITH PROJECT DOCUMENTS AND ALL LOCAL, STATE AND FEDERAL LAWS AND REGULATIONS. EROSION CONTROL MEASURES SHALL BE EMPLOYED TO REDUCE EROSION OF SLOPES AND SILTATION OF OFF-SITE OUTFALLS AND TRIBUTARIES.
- 8. UPON SIGNS OF CONCENTRATED FLOW BY EVIDENCE OF GULLYING OR RILLING IN DISTURBED AREAS, STAWBALES AND/OR STONE CHECK DAMS SHALL BE PLACED IN THESE AREAS, SPACED EVERY 50' IN THE UPGRADIENT SLOPE.
- ALL DISTURBED AREAS (UNLESS OTHERWISE NOTED) SHALL BE RE-ESTABLISHED WITH A 50/50 MIX OF "NEW ENGLAND CONSERVATION/WILDLIFE MIX" AND "NEW ENGLAND EROSION CONTROL/RESTORATION MIX FOR DRY SITES" FROM NEW ENGLAND WETLAND PLANTS, INC. OR APPROVED EQUAL. SEE ESTABLISHED GUIDELINES FOR SEED MIX BELOW FOR MORE

ESTABLISHED GUIDELINES FOR SEED MIX

NEW ENGLAND WETLAND PLANTS, INC. 820 WEST STREET, AMHERST, MA 01002 (413) 548-8000

- 1. ALL DISTURBED AREAS (UNLESS OTHERWISE NOTED) SHALL BE RE-ESTABLISHED WITH A 50/50 MIX OF "NEW ENGLAND CONSERVATION/WILDLIFE MIX" AND "NEW ENGLAND EROSION CONTROL/RESTORATION MIX FOR DRY SITES" FROM NEW ENGLAND WETLAND PLANTS, INC. OR APPROVED EQUAL.
- 2. THE MIX PROVIDES A PERMANENT COVER OF GRASSES. WILDFLOWERS AND LEGUMES TO PROVIDE BOTH GOOD EROSION CONTROL AND WILDLIFE HABITAT VALUE. THIS MIX IS DESIGNED TO BE A NO MAINTENANCE SEEDING, AND IT IS APPROPRIATE TO CUT AND FILL SLOPES, DETENTION BASIN SLOPES, AND DISTURBED AREAS ADJACENT TO COMMERCIAL AND RESIDENTIAL PROJECTS. ALWAYS APPLY ON CLEAN BARE SOIL. THE MIX MAY BE APPLIED BY HYDRO-SEEDING, BY MECHANICAL SPREADER, OR ON SMALL SITES IT CAN BE SPREAD BY HAND. LIGHTLY RAKE, OR ROLL TO ENSURE PROPER SEED TO SOIL CONTACT. BEST RESULTS ARE OBTAINED WITH A SPRING SEEDING. LATE SPRING THROUGH EARLY SUMMER SEEDING WILL BENEFIT WITH A LIGHT MULCHING OF WEED-FREE STRAW TO CONSERVE MOISTURE. IF CONDITIONS ARE DRIER THAN USUAL, WATERING WILL BE REQUIRED. LATE FALL AND WINTER DORMANT SEEDING REQUIRE AN INCREASE IN THE SEEDING RATE. FERTILIZATION IS NOT REQUIRED UNLESS THE SOILS ARE PARTICULARLY INFERTILE. PREPARATION OF A CLEAN WEED FREE SOIL SURFACE IS NECESSARY FOR OPTIMAL RESULTS.

SEED BED PREPARATION:

REMOVE ALL INVASIVE SPECIES, TILL EXISTING SOIL AND RAKE SMOOTH. APPLY 3" OF COMPOSTED LEAF LITTER. ALL AREAS WHERE ROOTS HAVE BEEN GRUBBED SHALL BE TILLED.

SEED APPLICATION AND RATE:

THE IDEAL PLANTING DEPTH IS 1/4-1/2". UNDER IDEAL CONDITIONS SEEDS LAYING ON THE SURFACE WILL GERMINATE. RECOMMENDED APPLICATION RATE FOR SEEDING IS 1 LBS PER 1,750 SQUARE FEET.

FOR FALL INSTALLATION. SEED BETWEEN AUGUST 15 AND SEPTEMBER 10. FOR SPRING INSTALLATION, SEED AS EARLY AS POSSIBLE SOMETIME BETWEEN APRIL 15 AND MAY 10.


FERTILIZATION AND SOIL REQUIREMENTS: REFER TO MANUFACTURERS RECOMMENDATIONS

GENERAL MAINTENANCE:

REFER TO MANUFACTURERS RECOMMENDATIONS

ESTABLISHMENT:

REFER TO MANUFACTURERS RECOMMENDATIONS




1. BALES TO BE TIED WITH ORGANIC FIBER TWINE ONLY NO PLASTIC OR WIRE.

2. STRAWBALES TO BE SECURED WITH A MINIMUM OF TWO (2) 1" x 1" WOODEN STAKES PER BALE DRIVEN 18" MIN. INTO GRADE.

DOUBLE ROW STRAWBALE WITH SILT FENCE BARRIER

(NOT TO SCALE)




PROPOSED SWALE FLOW NOTE: KEY STONE INTO PROPOSED SWALE AND EXTEND

IT BEYOND THE ABUTMENTS A MINIMUM OF 18" TO PREVENT FLOW AROUND THE CHECK DAM -CHECK DAMS TO BE PLACED EVERY 100 FEET, AND SHALL BE COMPRISED OF 20-LB. STONES AND 4"-7" STONE IN LARGER EXPOSED OPENINGS

<u>TYPICAL STONE CHECK DAM</u>


(NOT TO SCALE)




GRAVEL STONE TRENCH DETAIL



EROSION CONTROL BLANKET. OR APPROVED EQUAL (NOT TO SCALE)





UNION END VIEW

SECTION END VIEW

FilterMitt TM COMPONENTS

100% organic hessian.

FiberRoot Mulch TM FILLER INGREDIENT: • A BLEND OF COARSE AND FINE COMPOST AND SHREDDED • PARTICLE SIZES: 100% PASSING A 3" SCREEN; 90-100% PASSING A 1" SCREEN; 70-100% PASSING A 0.75" SCREEN; 30-75% PASSING


A 0.25" SCREEN. • WEIGHT: APPROX. 310 LBS./CU.YD. (AVE. 11.5 LBS./L.F.)


> For more information visit: <u>www.groundscapesexpress.com</u>or contact us at: Groundscapes Express, Inc.

> > P.O. Box 737 Wrentham, MA 02093 (508) 384-7140

FILTERMITT

(NOT TO SCALE)






FilterMitt *** INSTALLATION:

WITH THE NEWEST TECHNOLOGY AND EQUIPMENT, SECTIONS CAN BE CONSTRUCTED ON SITE IN LENGTHS FROM 1' TO 100'.

SECTIONS CAN ALSO BE DELIVERED TO THE SITE IN LENGTHS FROM 1' TO 8'.

THE FLEXIBILITY OF FilterMitt M ALLOWS IT TO CONFORM TO ANY CONTOUR OR TERRAIN WHILE HOLDING A SLIGHTLY ROUND SHAPE AT 8" HIGH BY 8" WIDE.

WHERE SECTION ENDS MEET, THERE SHALL BE AN OVERLAP OF 6" OR GREATER.



VARIES GRADE 6" PROPOSED SUBGRADE COMMON *BORROW* INSTALL RIPRAP EROSION CONTROL UPGRADIENT POST BLANKET TO BE CONSTRUCTION USED ON 2:1 SLOPES DOWN GRADIENT OF TEMPORARY SEDIMENTATION BASIN

(NOT TO SCALE)

SEDIMENTATION

BASINS

TEMPORARY SEDIMENTATION BASINS ARE TO BE INSTALLED IN LOCATIONS UPSTREAM OF ANY EROSION CONTROL BARRIERS WHERE EXCESS SEDIMENT IS OBSERVED DURING THE CONSTRUCTION PROCESS. CONTRACTOR TO LOCATE TEMPORARY SEDIMENTATION BASINS AS THEY DEEM NECESSARY TO PREVENT SEDIMENT FROM LEAVING THE LIMIT OF WORK. AS THE SITE STABILIZES, THE TEMPORARY SEDIMENTATION BASINS CAN BE REMOVED AND BROUGHT TO

FINISHED GRADES.

(NOT TO SCALE)

DWG. No. 6091_SITE(PENNY).DWG [ECP NOTES

FOR PERMITTING ONLY NOT FOR CONSTRUCTION

NOTE: FOR DETAILS NOT DEPICTED HEREON. REFER TO MASSDOT STANDARD SPECIFICATIONS AND CONSTRUCTION DETAILS.

5R I NOTE

MSBU, (HAMI

FEBRUARY 19, 201 NOT TO SCALE

SHEET No. 15 of 16

PROJECT No.

